

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate showing the quantities for constructing wards and kitchen in the Civil Hospital compound at Tumkur.

No.	Items of work	Per	Quantity	
			Wards	Kitchen
1	Earthwork excavation and filling in basement	C. yd.	78	9
2	Concrete with burnt stone in chunam	C. ft.	441	...
3	Burnt stone in mortar	"	2,618	...
4	Burnt stone in mud	"	3,941	112
5	Burnt brick in mortar	"	...	516
6	Burnt brick in mud	"	...	10
7	Archwork brick in mortar	"	...	23
8	Burnt stone slabs	S. ft.	766	11'66
9	Plastering with mortar	Sqr.	59'33	11'66
10	White and color washing	C. ft.	127	18'47
11	Teakwood work wrought and put up with wood oiling	S. ft.	254	18
12	Teakwood doors panelled with iron works, etc., complete	"	81	...
13	Teakwood pattered doors with iron works, etc., complete	"	...	6
14	Teakwood windows with bolt panelled and glazed shutters with iron bars, etc., complete	"	...	101
15	Teakwood windows with battened shutters and iron work, etc.	"	...	72
16	Teakwood ventilators with glazed shutters, iron works, etc.	"	...	23'05
17	Teakwood shelves with panelled shutters, iron works, etc.	Sqr.	84	12
18	Roofing with 1st class Mangalore tiles over teak reapers, etc.	R. ft.	9	...
19	Ridge tiles set in mortar	No.	167	41
20	Burnt stone pillars with base and capitals	R. ft.	...	35
21	Ornamental eave boards	"	...	132
22	Teakwood plain eave board	"	...	6'27
23	Cornice 1' thick including plastering	"	...	1'18
24	Dwarf wall over gable ends including finials	"	...	...
25	Flooring with 1st class Mangalore tiles over 3" concrete and cement pointing	Sqr.	6'02	...
26	Flooring with Cuddappa slabs on 3" concrete bed and cement pointing	"	...	...
27	Constructing sink with iron pipe, etc.	Lump	sum Rs.	15
28	Chunam border	R. ft.	...	0'46
29	Terracing	Sqr.	...	...
30	Constructing drains to lead off water from bath and latrine	Lump	sum	0'48
31	Chocolate painting	Sqr.	12'82	...
32	Clearing site and levelling ground	Lump	sum Rs.	...
33	Teakwood planks with zinc sheets for valleys	S. ft.	156	...
34	Pointing to basement	Sqr.	5'00	0'55
35	Mortar pestal stone	Lump	sum Rs.	...

N. G. KRISHNA IYENGAR,
Executive Engineer.

DEPARTMENT OF INDUSTRIES AND COMMERCE.

SUPPLY OF TOOLS.

Notice is hereby given, that sealed tenders will be received at the office of the Director of Industries and Commerce up to 12 noon, 18th February 1918 for the supply of tools required for the Department. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1918.

2. Tenders should be submitted on printed forms which may be obtained from the Director. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3. Each tender must be accompanied by a deposit of Rs. 200 in cash as earnest money and be superscribed "Tender for supply of tools required for the Department of Industries and Commerce"; in default of which tenders will be rejected.

4. The final acceptance of any tender will rest with the Director who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

6. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Director's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

7. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate of the probable cost of tools, etc., required for each district for the use of Superintendents and Assistant Superintendents.

Particulars	Per	Quantity	Particulars	Per	Quantity
Steel tape, 50 feet	Each	1	Inside and outside callipers	Set	1
Spirit level, 12"		1	Ball pane hammers 1, 2, 4 and 7 lbs.	lbs.	14
Gas die box $\frac{1}{2}$ " to 2" complete	Set	1	Straight edge, 8 feet	Each	1
Witworth's die box $\frac{1}{2}$ " to $\frac{3}{4}$ " dies with taps, wrenches, etc., complete.	"	1	Assorted files a set of 6 of 4"	Set	1
Steel square 12"	"	1	Pipe cutter 2" to 4" (2" to 6" if not available.)	"	1
Bench vice 4" jaw	"	20	One set spanners from $\frac{1}{2}$ " to 2"	Set	1
Pipe wrench up to 4"	"	1	Pulley block 1 ton (weighing with chain).	Each	1
Stillson's pipe wrench 18"	"	1	Lifting and traversing jack (8 ton capacity).	"	1
10" Ratchet, with bits (7)	"	1	Bottle jack 6 tons	"	1
Foot rule 2 feet, 4 fold	"	1	Blacksmiths bellows 24"	"	1
Pliers	"	1			

WORKSHOP AT CHITALDRUG AND SHIMOGA.

Notice is hereby given that sealed tenders will be received at the office of the Director of Industries and Commerce up to 12 noon on 18th February 1918 for the construction of Workshop at Chitaldrug District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1918.

2. The plans, detailed estimate and conditions may be seen at the office of Superintendent of Industries at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Director. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for the construction of District workshop, at Chitaldrug", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Director who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be intimated to him in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned. General abstract of cost of constructing District Workshop for the Industries and Commerce, Department at Chitaldrug and Shimoga.

Items of work	Per	Constructing office and store rooms	Constructing machinery shed	Constructing stock rooms and blacksmith's shed	Constructing compound wall
		Quantity	Quantity	Quantity	Quantity
Earthwork excavation	C. yd.	37	28	37	20
Burnt stone in mortar	C. ft.	1,346	946	1,252	
Burnt brick in mortar		2,054	716	1,997	
Teakwood panelled doors with iron works, iron cleats, etc., complete.	S. ft.	45		86	
Teakwood windows of double shutters (glazed and panelled shutters) with iron bars, iron work, iron cleats, etc.	"	96			
Burnt stone slabs 6" thick, dressed, complete	"	165	29	106	
Do 4" do do	"		712		
Teakwood wrought and put up with wood oiling, etc., complete.	C. ft.	64.32	98.68	61.51	
Roofing with 1st class Mangalore tiles on teak reapers, etc., complete.	S. ft.	12.81	12.24	18.12	
Ridge tiles set in mortar and cement pointing	R. ft.	63	45	68	
Ornamental teakwood board		166	143	167	
Plastering with chunam	Sq.	56.64	16.52	39.45	
Flooring with Cudappah slabs on 3" concrete bed and cement pointing	"	4.91		4.4	
Painting (double coating)		4.5	2.5	2.10	
Gravel filling, tamping, watering, etc., complete	C. yd.	3		4.5	
White and colour washing	L. S.	1			
Clearing and levelling site	L. S.	1			
Finely dressed slabs 4" thick and edges chamfered and fitted on mortar.	S. ft.		123		
Concrete in chunam			178		
Pointing in cement	Sq.		2,445		
Drilling holes in slabs	No.		20		
Iron work for trusses			5		
Teakwood windows battened, etc., complete				48	
Cutting grooves on top of stone pillars				1.14	
Burnt stone in mud	C. ft.			690	
Burnt brick in mud				1,128	
Coping with B. brick in chunam and chunam plastering.	R. ft.			181	
Zinc sheet iron framed gate with hinges and cutting grooves in slabs.	S. ft.			48	

V. RANGASWAMIENGAR,

Offg. Director of Industries and Commerce.